

ASTM E 2140 TEST REPORT

Rendered to:

SHEFFIELD METALS INTERNATIONAL

MODEL DESIGNATION: SMI 1-1/2" Mechanical Seam over Plywood PRODUCT TYPE: Standing Seam Roof System (24 Ga. Steel)

This report contains in its entirety:

Cover Page: 1 page **Report Body:** 5 pages

No. 53820

STATE OF

CONAL E

Digitally Signed by: Vinu Abraham

2012.03.12 17:28:50

-04'00'

Report No.: B5170.23-450-18

Test Date: 2/17/12 **Report Date:** 3/2/12

Test Report Retention End Date: 3/2/16



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454 F: 561.881.0075

Test Report #: B5170.23-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 1C Page: 1 of 5

Sheffield Metals International

SMI 1-1/2" Mechanical Seam over Plywood (ASTM E 2140) Test Report #: B5170.23-450-18

1 0	MANUFACTURER'S IDENTIFIC	CATTON
1-0	MANUFACIURER'S IDENTIFIC	LATION

1.1 Name of Applicant: Sheffield Metals International

> 5467 Evergreen Parkway Sheffield Village, OH 44054

Voice: 904.413.7425

1.2 Contact Person: Jim Mitchell

2.0 LABORATORY IDENTIFICATION

2.1 Test Notification #:

Miami-Dade County (05-1014-89); Florida Building Code Lab Certifications: 2.2

(TST1527); IAS (TL-244); AAMA; WDMA; Keystone Certifications; Texas Department of Insurance

SCOPE OF WORK 3.0

Sheffield Metals Miternational retained Architectural Testing, Inc. 3.1 **Introduction:**

(ATI) to conduct water infiltration testing on their SMI 1-1/2" Mechanica Seam over Plywood System per the requirements of

ASTM.

3.2 Report Information: Table provides the test date for this specimen.

Table 1: Specimen Test Date

Mock-Up	Specimen #	Test Date
SMI 1-1/2" Mechanical Seam over Plywood	1C	2/17/2012

4.0 PRODUCT IDENTIFICATION


Standing Seam Roof System 4.1 **Product Type:**

Model Designation SMI 1-1/2" Mechanical Seam over Plywood 4.2

69" (wide) x 113" (long) - Structural roof frame 4.3 Overall Size:

General Description: This specimen consisted of a 69" x 113" structural roof frame 4.4 fabricated from 2x (nominal) wood with intermediate rafters spaced 24" on center. This assembly was sheathed with a single layer of 1/2" (nominal) structural CDX Plywood. This was followed by a single layer each of felt paper and moisture/fire barrier. The roofing panels were fastened over the moisture/fire

4.5 Sample Source: Sheffield Metals International provided the test specimen.



Test Report #: B5170.23-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

Specimen #: 1C

Page: 2 of 5

·9/·

5.0 **COMPONENT DESCRIPTION**

Structural Support Frame: 5.1

Table 2 provides the structural support frame components used for the test specimen.

Table 2: Structural Support Frame Components

	rable El Stractaral Support Frame Components
Item	Description
Intermediate rafters	There were four (4) intermediate rafters used in this specimen - specied 24" on center – that were each fabricated from 2x southern Yellow Pine fimber planks.
Plywood substrate	A single layer of 1/2" (minimum 15/32" thick) CDX Plywood was utilized across the entire surface of this specimen.

5.2

Table 3 provides a description of the accessories used in the test speciment RNA


Item	Description
Felt paper	30# Asphalt saturated organic paper (ASTM D226) meeting type II requirements
Moisture/fire barrier	VersaShield®
Sealant	TFC 100™ High Performance Commercial Grade Sealant

5.3 Metal Roof System:

Table 4 provides the metal roof system components used in the test specimen.

Table 4: Metal Roof System Components

Table 1: Metal tool System Components				
Item	Overall Cross-Section	Material	Coil Width	Description
Mechanical Seam Panel	Please see part dawing labeled "SMI 1/2" Mechanical Seam Profile" for dimensions	24 ga. steel	20"	Each panel had an effective covering width of 16". Each finished roof panel was 111" (long) and featured two (2), 1-1/2" vertical legs (one w/return flap).
Clip Assembly (Butterfly Base 1-1/2" – Part # 1126602)	1.000 x 1.250" x 4.500" (long)	22 ga. G-90 galvanized steel	N/A	Each expansion-type butterfly panel clip consisted of a "base" and a "tab" that were each fabricated from two
Clip Assembly (Butterfly Tab 1 122" – Part # 1103095)	5.000" (long) x 0.910" (tall) with two return flaps that were 0.400" (wide)	24 ga. G-90 galvanized steel	N/A	different thicknesses of steel. Each clip "base" had two holes capable of accommodating #10 pancake head screws.



Test Report #: B5170.23-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016 Specimen #: 1C

Page: 3 of 5

6.0 SPECIMEN CONSTRUCTION

Table 5 provides the specimen construction.

Table 5: Specimen Construction

Table 5: Specimen Construction				
Location	Description <u>20</u> 1.			
Plywood sheathing to structural	s spaced 4" on center at the perimeter			
support frame				
Felt paper	A single layer of felt paper with 4" laps attached to the plywood substrate with 0.120" x 1-1/4" galvanized smooth shank roofing nails with 32 ga. tin caps Spaced 8" on center (staggered) at the field Spaced 5" on center at the top and bottom of the specimen Spaced 7" on center of the sides of the specimen Spaced 6" on center of the sides of the specimen Spaced 6" on center at the overlap locations			
Moisture/fire barrier	A single layer of VersaShield® with 4" lans was theyed in place across the top of			
Roof panel	Each of the four (4) full finished roof panels reatured an inside leg and an outside leg. These legs were overlapped around a butterfly clip base/tab assembly. These clip assemblies were spaced 40 and 24" from each panel end and at 24" on center thereafter. Each clip was mechanically attached to the plywood substrate using two (2), #10 x 1" Weather Gard® pancake head screws (Type A). The legs were then mechanically seamed 180 degrees.			
Sealant	A 1/8" bead of TFC 100™ high Performance Commercial Grade Sealant was applied to the first 90 degree bend closest to the vertical leg of the female side of each roof panel. The perimeter of the panel assembly was fully sealed to the structural support trame.			
Panel edges	The panel edges at the perimeter of the roof panel assembly were attached to the plywood substrate using a single row of $#10 \times 1$ " Weather Gard® pancake head screws (Type A) spaced at 6" on center.			
Panel ends	The panel ends at the perimeter of the roof panel assembly were attached to the plywood substrate using a single row of $\#10 \times 1\%$ Weather Gard® pancake head corews (Type A) spaced at 4% on center.			

7.0 TEST RESULT SUMMARY

Table 6 provides a summary of the test results for tests conducted per ASTM E 2140.

Table 6: Summary of Test Results

Specimen #	Test Method	Conclusion
1C	Water Infiltration Test (ASTM E2140)	PASS



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075
Architectural Testing ARCHTEST.COM

Test Report #: B5170.23-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 1C Page: 4 of 5

8.0 TEST SEQUENCE

Table 7 provides the test sequence for the specimen.

Table 7: Test Sequence

	able 7. Test sequence
	Specimen # 1C
1.	Water Infiltration Test

9.0 TEST RESULTS

9.1 Water Infiltration Test

9.1.1 Results

Table 4 provides the results for the water infiltration test.

Table 2: Water Infiltration Test Results

Test Duration (hours)	Water Pressure Head (in.)	Conclusion
1	6 +/-0.2	"Kr.
3	6 +/-0.2	(R) Pass
6	6 +/-0.2	

9.1.2 Conclusion

ATI observed zero (0) water infiltration through the test specimen; as such, this test specimen satisfies the requirements of ASTM E 2140.

10.0 CERTIFICATION AND DISCLALMER STATEMENT

All tests performed on this test specimen were conducted in accordance with the specifications of the applicable codes, standards and test methods listed below by ATI. ATI does not have, nor does it intend to acquire or will it acquire, a financial interest in any company manufacturing or distributing products tested at ATI. ATI is not owned, operated or controlled by any company manufacturing or distributing products it tests. This report is only intended for the use of the entity named in Section 1.0 of this report. Detailed assembly drawings showing panel/clip thicknesses, panel/clip profiles, accessories, fasteners and all other applicable layouts are on file and have been compared to the test specimen submitted. ATI will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by ATI for the entire test record retention period.

If test specimen contains glazing, no conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen can be made. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so maked herein and relates only to the specimen tested. This report may not be reproduced, except in full, without the written approval of ATI.

11.0 APPLICABLE CODES, STANDARDS, AND TEST METHODS

ASTM E 2140 – Standard Test Method for Water Penetration of Metal Roof Panel Systems by Static Water Pressure Head



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075 Architectural Testing ARCHTEST.COM Test Report #: B5170.23-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 1C Page: 5 of 5

12.0 WITNESSES (ALL OR PARTIAL)

.0 W	ITNESSES (ALL OR PAI	RTIAL)	
Vind Jeff Kris Joh	u J. Abraham, P.E. [·] McGovern stin Norville, E.I. n Spallina	Vice President – Southeast Region Director – Regional Operations Operations Engineer Technician Regional Operations Operations Engineer Technician Regional Operations Operati	ATI ATI ATI ATI ATI ATI
		, in the second	ATHE SMITES
		WRITEHONSEN	
		WANTHOUT V.	
		COROLLED IN AMIN	
	WIFED	8 th.	
	ast CHANGED,		
	ORISMOTO		
THISR			

ENGINEER OF RECORD

Digitally Signed by: Vinu Abraham
Vinu J. Abraham, P.E.

3/2/2012

REPORT WRITER

Angela Abramczyk

3/2/2012