

# UL 580 & UL 1897 TEST REPORT

### Rendered to:

### SHEFFIELD METALS INTERNATIONAL

MODEL DESIGNATION: SMI 1-1/2" SnapLock 550 over Plywood PRODUCT TYPE: Standing Seam Roof System (24 Ga. Steel)

This report contains in its entirety:

**Cover Page:** 1 page **Report Body:** 6 pages

No. 53820 ★

STATE OF

ONALEN

Digitally Signed by: Vinu Abraham

2012.03.12 17:31:42

-04'00'

**Report No.:** B5925.01-450-18

**Test Date:** 2/10/12 **Report Date:** 3/2/12

**Test Report Retention End Date:** 3/2/16



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454 F: 561.881.0075

Test Report #: B5925.01-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 1 Page: 1 of 6

# Sheffield Metals International

SMI 1-1/2" SnapLock 550 over Plywood (UL 580 & UL 1897) Test Report #: B5925.01-450-18

1 0	MANUFACTURER'S IDENTIFICAT	CTAN
1 -()	MANUFACIURER'S IDENIIFICA	HUN

1.1 Name of Applicant: Sheffield Metals International

> 5467 Evergreen Parkway Sheffield Village, OH 44054 Voice: 904.413.7425

1.2 Contact Person: Jim Mitchell

2.0 LABORATORY IDENTIFICATION

2.1 Test Notification #:

Miami-Dade County (05-1014(3)); Florida Building Code Lab Certifications: 2.2

> (TST1527); IAS (TL-244); AAMA; WDMA; Keystone Certifications; Texas Department of Insurance

**SCOPE OF WORK** 3.0

Sheffield Metals Metals Ternational retained Architectural Testing, Inc. 3.1 **Introduction:** 

(ATI) to conduct roof uplift testing on their SMI 1-1/2" SnapLock 550 over two od System per the requirements of Underwriters

Laboratories Inc.

Table provides the test date for this specimen. 3.2 Report Information:

Table 1: Specimen Test Date

u	rable 11 opecimen	. Cot Bate	
۰	Mock-Up	Specimen #	Test Date
	SMI 1-1/2" SnapLock 550 over Plywood	1	2/10/2012

#### 4.0 PRODUCT IDENTIFICATION

Standing Seam Roof System 4.1 Product Type:

Model Designation SMI 1-1/2" SnapLock 550 over Plywood 4.2

4.3 Overall Size: 120" (wide) x 120" (long) - Panel assembly

General Description: This specimen consisted of a 120" x 120" structural roof frame 4.4

fabricated from 2x (nominal) wood with intermediate rafters spaced 24" on center. This assembly was sheathed with a single layer of 1/2" (nominal) structural CDX Plywood. This was followed by a single layer each of felt paper and moisture/fire

barrier. The roofing panels were fastened over the moisture/fire

4.5 Sample Source: Sheffield Metals International provided the test specimen.



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075 Architectural Testing ARCHTEST.COM Test Report #: B5925.01-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 1 Page: 2 of 6

#### 5.0 **COMPONENT DESCRIPTION**

### 5.1 **Structural Support Frame:**

Table 2 provides the structural support frame components used for the test specimen.

	Table 2: Structural Support Frame Components
Item	Description
Intermediate rafters	There were four (4) intermediate rafters used in this specimen - spaced 24" on center – that were each fabricated from 2x southern Yellow Pine finber planks.
Plywood substrate	A single layer of 1/2" (minimum 15/32" thick) CDX Plywood was utilized across the entire surface of this specimen.

### 5.2

Table 3 provides a description of the accessories used in the test speciment (ROM)

	1 4.5.5 5.7 1.5555551.55
Item	Description
Felt paper	30# Asphalt saturated organic paper (ASTM D226) meeting type II requirements
Moisture/fire barrier	Ve <b>rsa</b> Shield®

#### 5.3 Metal Roof System:

Table 4 provides the metal roof system components used in the test specimen.

Table 4: Metal Roossystem Components

Item	Overall Cross- Section	Material	Coil Width	Description
SnapLock 550 Panel	Please see part drawing labeled "SMI 1 ½" SnapLock 550 for dimensions	324 ga. steel	24"	Each panel had an effective covering width of 19". Each finished roof panel was 120" (long) and featured a male vertical leg that was 1-3/8" (high) and a female vertical leg that was 1-1/2" (high).
SnapLock 1-1/2" clip	1.610″(62.010″ x 2.000 (long)	20 ga. G-90 galvanized steel	N/A	Each clip had three (3) holes capable of accommodating #10 pancake head screws (although only two [2] of the holes were utilized for installation).

### SPECIMEN CONSTRUCTION 6.0

Table provides the specimen construction.

**Table 5: Specimen Construction** 

d	Location Description	
Ì	Plywood sheathing	2-1/2" x .131" EG ring shank nails spaced 4" on center at the perimeter
	to structural support frame	2-1/2" x .131" EG ring shank nails spaced 6" on center at the field



Test Report #: B5925.01-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 1 Page: 3 of 6

Table 5: Specimen Construction (continued)

Location	Description		
Felt paper	A single layer of felt paper with 4" laps attached to the plywood substrate with 0.120" x 1-1/4" galvanized smooth shank roofing nails with 32 ga. tin caps	Spaced 7" on center at the perimeter Spaced 8" on center (staggered) at the reld	
Moisture/fire barrier  A single layer of VersaShield® with 4" laps was tacked in place across the felt paper and was secured when the metal roofing was installed.			
Roof panel	Each finished roof panel was mechanically attached to the along the male leg using a series of SnapLock clips space panel end and at 24" on center thereafter. Each individe the male leg and secured to the plywood substrate using Weather Gard® pancake head screws (Type A). Once place, the female leg of the adjacent roof panel was and male leg of the panel.	ted 4" and 24" from each ual the was hooked over gravo (2), #10 x 1" the clips were secured in	
Partial panel cut edges	The partial panel cut edges at the perimeter of the roof panel assembly were attached to the plywood substrate using a single row of #10 x 1" Weather Gard® pancake head screws (Type A) spaced at on center.		
Panel ends	The panel ends at the perimeter of the poof panel assen plywood substrate using a single row of $\#10 \times 1''$ Weath screws (Type A) spaced at $4''$ on tenter.		

### 7.0 **TEST RESULT SUMMARY**

Table 6 provides a summary of the test results for all tests conducted per UL 580 and UL 1897.

Table 6 Summary of Test Results

Table 1 to 1 t				
Specimen #	TestoMethod	Conclusion		
	UL 580	PASS (Class 30,60, and 90)		
1	UL 1897 Maximum Combined Sustained Pressure	258.5		
	UL 1897 Combined Failure Pressure	273.5		

### TEST SEQUENCE 8.0

Table 700 vides the test sequence for the specimen.

Table 7: Test Sequence				
Specimen # 1				
1. UL 580 Class 30 Test				
2.	UL 580 Class 60 Test			
3. UL 580 Class 90 Test				
4.	UL 1897 Test			



6655 Garden Road Riviera Beach, FL 33404

P: 888.477.2454 F: 561.881.0075 Architectural Testing ARCHTEST.COM Test Report #: B5925.01-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 1 Page: 4 of 6

### 9.0 UL 580 TEST RESULTS

# 9.1 Class 30, 60 and 90 Test Load Data

The test results for the specimen are presented in the following tables. Tables 8, 9 and 10 provide the Class 30, 60 and 90 test load data, respectively.

Table 8: Class 30 Load Data

Test	Test Duration	Positive Pressure	Negative Pressure	Test
Phase	(min)	(psf)	(psf)	Status
1	5	0.0	16.2	PASS
2	5	13.8	16.2	RASS
3 <sup>1</sup>	60	13.8	8.1-27.7	PASS
4	5	0.0	24.2	PASS
5	5	20.8	24.2	PASS

<sup>1.</sup> Cyclic stage with 8-12 seconds per cycle.

Table 9: Class 60 Load Data

	Table 3: class 60 Edda Bata 201			
Test	Test Duration	Positive Pressure	Negative Pressure	Test
Phase	(min)	(psf)	(psf)	Status
1	5	0.0	32.3	PASS
2	5	27.7	32.3	PASS
3 <sup>1</sup>	60	27.7	16.2-55.4	PASS
4	5	0.0	40.4	PASS
5	5	34.6	40.4	PASS

<sup>1.</sup> Cyclic stage with 8-12 seconds per cycle.

Table 19: Class 90 Load Data

Test	Test Duration	Resitive Pressure	Negative Pressure	Test
Phase	(min)	(psf)	(psf)	Status
1	5	0.0	48.5	PASS
2	5	41.5	48.5	PASS
3 <sup>1</sup>	60	41.5	24.2-48.5	PASS
4	ر الأبي.	0.0	56.5	PASS
5	5	48.5	56.5	PASS

<sup>1.</sup> Cyclic stage with 8-12 seconds per cycle.

### 9.2 Remarks

A single layer of 2 ml flat polyethylene film was applied across the entire surface of the prepared roof deck in order to seal against air leakage. This plastic film contacted all surfaces of the panels and/or clips and did not interfere with air passage to the specimen or the movement of adjacent parts. No signs of faiture were noticed during class 30, 60, and 90 of the UL 580 test. No failures were observed in any components of the roof system or in any of the fasteners used to attach the roof system to the prepared structural roof frame.



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075
Architectural Testing ARCHTEST.COM

Test Report #: B5925.01-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 1 Page: 5 of 6

## **10.0 UL 1897 TEST RESULTS**

### 10.1 Failure Test Load Data

Table 11 provides the failure test load data.

Table 11: Detailed Test Results of the Optional Failure Test

Test	Pressure	Negative	Positive	Combined	_
Phase	Duration (min)	Pressure (psf)	Pressure (psf)	Pressure (psf)	Status
1	1	30	48.5	78.5	PASS
2	1	45	48.5	93.5	RASS
3	1	60	48.5	108.5	PASS
4	1	75	48.5	123.5	PASS
5	1	90	48.5	138,50	PASS
6	1	105	48.5	153,5	PASS
7	1	120	48.5	<del>95</del> 8.5	PASS
8	1	135	48.5	183.5	PASS
9	1	150	48.5	198.5	PASS
10	1	165	48.5	213.5	PASS
11	1	180	48.5	228.5	PASS
12	1	195	485	243.5	PASS
13	1	210	¥8.5	258.5	PASS
14	1	225	48.5	273.5	FAIL


### 10.2 Remarks

The highest combined pressure the test specimen successfully resisted for 1 minute was 258.5 psf. At a combined pressure of 273.5 psf the specimen had clip failure causing the rib to crease.

### 11.0 CERTIFICATION AND DISCLAIMER STATEMENT

All tests performed on this test specimen were conducted in accordance with the specifications of the applicable codes, standards and test methods listed below by ATI. ATI does not have, nor does it intend to acquire or will it acquire a financial interest in any company manufacturing or distributing products tested at ATI. ATI is not owned, operated or controlled by any company manufacturing or distributing products it tests. This port is only intended for the use of the entity named in Section 1.0 of this report. Detailed assembly drawings showing panel/clip thicknesses, panel/clip profiles, accessories, fasteners and all other applicable layouts are on file and have been compared to the test specimen submitted. ATI will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by ATI for the entire test record retention period.

The strain specimen contains glazing, no conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen can be made. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen tested. This report may not be reproduced, except in full, without the written approval of ATI.



Test Report #: B5925.01-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 1 Page: 6 of 6

# 12.0 APPLICABLE CODES, STANDARDS, AND TEST METHODS

UL 580 - Tests for Uplift Resistance of Roof Assemblies UL 1897 - Uplift Tests for Roof Covering Systems

# **13.0**

ATT ATT LENGTH AND LETTER OF THE PROPERTY OF T

ENGINEER OF RECORD

ally Signed by: Vinu Abraham
Vinu J. Abraham, P.E.

REPORT WRITER

Angela Abramczyk

3/2/2012 3/2/2012