

UL 580 & UL 1897 TEST REPORT

Rendered to:

SHEFFIELD METALS INTERNATIONAL

MODEL DESIGNATION: SMI 1-3/4" SnapLock over Plywood PRODUCT TYPE: Standing Seam Roof System (24 Ga. Steel)

This report contains in its entirety:

Cover Page: 1 page **Report Body:** 6 pages

STATE OF

No. 53820

SONALEN

Digitally Signed by: Vinu Abraham

2012.03.12 15:31:59

-04'00'

Report No.: B5170.08-450-18

Test Dates: 12/7-8/11 **Report Date:** 3/2/12

Test Report Retention End Date: 3/2/16



Test Report #: B5170.08-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016 Specimen #: 4

Page: 1 of 6

Sheffield Metals International

SMI 1-3/4" SnapLock over Plywood (UL 580 & UL 1897) Test Report #: B5170.08-450-18

1.0 MANUFACTURER'S IDENTIFICATION

1.1 Name of Applicant: Sheffield Metals International

5467 Evergreen Parkway Sheffield Village, OH 44054

Voice: 904.413.7425

1.2 <u>Contact Person:</u> Jim Mitchell

2.0 LABORATORY IDENTIFICATION

2.1 Test Notification #: N/A

2.2 <u>Lab Certifications</u>: Miami-Dade County (05-101+07); Florida Building Code

(TST1527); IAS (TL-244); AAMA; WDMA; Keystone Certifications; Texas Department of Insurance

3.0 SCOPE OF WORK

3.1 <u>Introduction</u>: Sheffield Metals International retained Architectural Testing, Inc.

(ATI) to conduct roof uplift testing on their SMI 1-3/4" SnapLock over Plywood System per the requirements of Underwriters

Laboratories Inc.

3.2 Report Information: Table 1 provides the test dates for this specimen.

Table 1: Specimen Test Dates

Mock-Up	Specimen #	Test Dates
SMI 1-3/4" SnapLock over	4	12/7/2011 -
Plywood	7	12/8/2011

4.0 PRODUCT IDENTIFICATION

4.1 <u>Product Type</u>: Standing Seam Roof System

4.2 <u>Model Designation</u> SMI 1-3/4" SnapLock over Plywood

4.3 <u>Overall Size</u>: 120" (wide) x 120" (long) – Panel assembly

4.4 <u>General Description</u>: This specimen consisted of a 120" x 120" structural roof frame

fabricated from 2x (nominal) wood with intermediate rafters spaced 24" on center. This assembly was sheathed with a single layer of 1/2" (nominal) structural CDX Plywood. This was followed by a single layer each of felt paper and moisture/fire

barrier. The roofing panels were fastened over the moisture/fire

barrier.

4.5 <u>Sample Source</u>: Sheffield Metals International provided the test specimen.

6655 Garden Road Test Report #: B5170.08-450-18 Report Date: 3/2/2012 Riviera Beach, FL 33404

Test Report Retention End Date: 3/2/2016

Specimen #: 4 Page: 2 of 6

5.0 **COMPONENT DESCRIPTION**

5.1 **Structural Support Frame:**

Table 2 provides the structural support frame components used for the test specimen.

Table 2: Structural Support Frame Components

	rable 2. of actard, capport frame compensions
Item	Description
Intermediate rafters	There were four (4) intermediate rafters used in this specimen - specied 24" on center – that were each fabricated from 2x southern Yellow Pine Lymber planks.
Plywood substrate	A single layer of 1/2" (minimum 15/32" thick) CDX Plywood was utilized across the entire surface of this specimen.

5.2

Table 3 provides a description of the accessories used in the test speciment.

Item	Description
Felt paper	30# Asphalt saturated organic paper (ASTM D226) meeting type II requirements
Moisture/fire barrier	V <mark>e</mark> rsaShield [®]

5.3 Metal Roof System:

Table 4 provides the metal roof system components sed in the test specimen.

Table 4: Metal Roof System Components

Item	Overall Cross- Section	Matterial	Coil Width	Description
SnapLock Panel	Please see part drawing labeled "SMI 1 34" Snaplock Profile for dimensions	24 ga. steel	24"	Each panel had an effective covering width of 18". Each finished roof panel was 120" (long) and featured a male vertical leg that was 1-5/8" (high) and a female vertical leg that was 1-25/32" (high).
SnapLock 1-3/4" clip (Part # M0407)	1.875" x 2.010" x 3.500 (long)	18 ga. G-90 galvanized steel	N/A	Each clip had two (2) holes capable of accommodating #10 pancake head screws.

6.0 SPECIMEN CONSTRUCTION

Table 5 prevides the specimen construction.

Table 5: Specimen Construction

	1 able 51 specimen construction			
_ <	O Eocation	Description		
Plywood sheathing to structural support frame	2-1/2" x .131" EG ring shank nails spaced 4" on center at the perimeter			
		2-1/2" x .131" EG ring shank nails spaced 6" on center at the field		



Test Report #: B5170.08-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 4 Page: 3 of 6

Table 5: Specimen Construction (continued)

Location	Description		
Felt paper	A single layer of felt paper with 4" laps attached to the plywood substrate with 0.120" x 1-1/4" galvanized smooth shank roofing nails with 32 ga. tin caps	Spaced 7" on center at the perimeter Spaced 8" on center (staggered) at the field	
Moisture/fire barrier	Moisture/fire barrier A single layer of VersaShield® with 4" laps was tacked in place across the top of the felt paper and was secured when the metal roofing was installed.		
Roof panel	Each finished roof panel was mechanically attached to the plywood substrate along the male leg using a series of SnapLock clips spaced 4" and 24" from each panel end and at 24" on center thereafter. Each individual was hooked over the male leg and secured to the plywood substrate using two (2), #10 x 1" Weather Gard® pancake head screws (Type A). Once the clips were secured in place, the female leg of the adjacent roof panel was snap-locked over the clips and male leg of the panel.		
Partial panel cut edges	The partial panel cut edges at the perimeter of the roof attached to the plywood substrate using a single row of pancake head screws (Type A) spaced at A" on center.		
Panel ends	The panel ends at the perimeter of the roof panel assen plywood substrate using a single row of $\#10 \times 1\%$ Weath screws (Type A) spaced at 4% on tenter.	•	

7.0 TEST RESULT SUMMARY

Table 6 provides a summary of the test results for all tests conducted per UL 580 and UL 1897.

Table Summary of Test Results

Table of the same				
Specimen #	Testemethod	Conclusion		
	UL 580	PASS (Class 30,60, and 90)		
4	UL 1897 Maximum Combined Sustained Pressure	228.5		
	UL 1897 Combined Failure Pressure	243.5		

8.0 TEST SEQUENCE

Table Tovides the test sequence for the specimen.

Table 7: Test Sequence				
Specimen # 4				
1. UL 580 Class 30 Test				
2.	UL 580 Class 60 Test			
3.	UL 580 Class 90 Test			
4.	UL 1897 Test			



6655 Garden Road Riviera Beach, FL 33404

P: 888.477.2454 F: 561.881.0075 Architectural Testing ARCHTEST.COM Test Report #: B5170.08-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 4 Page: 4 of 6

9.0 UL 580 TEST RESULTS

9.1 Class 30, 60 and 90 Test Load Data

The test results for the specimen are presented in the following tables. Tables 8, 9 and 10 provide the Class 30, 60 and 90 test load data, respectively.

Table 8: Class 30 Load Data

Test	Test Duration	Positive Pressure	Negative Pressure	Test
Phase	(min)	(psf)	(psf)	Status
1	5	0.0	16.2	PASS
2	5	13.8	16.2	RASS
3 ¹	60	13.8	8.1-27.7	PASS
4	5	0.0	24.2	PASS
5	5	20.8	24.2	PASS

^{1.} Cyclic stage with 8-12 seconds per cycle.

Table 9: Class 60 Load Data

	Table 3: class 66 Edda Data				
Test	Test Duration	Positive Pressure	Negative Pressure	Test	
Phase	(min)	(psf)	(psf)	Status	
1	5	0.0	32.3	PASS	
2	5	27.7	32.3	PASS	
3 ¹	60	27.7	16.2-55.4	PASS	
4	5	0.0 4	40.4	PASS	
5	5	34.6	40.4	PASS	

^{1.} Cyclic stage with 8-12 seconds per cycle

Table 10: Class 90 Load Data

	Talle Ito. Class 30 Load Data				
Test	Test Duration	ositive Pressure	Negative Pressure	Test	
Phase	(min)	(psf)	(psf)	Status	
1	5	0.0	48.5	PASS	
2	5,4	41.5	48.5	PASS	
3 ¹	60	41.5	24.2-48.5	PASS	
4	1(2/3)	0.0	56.5	PASS	
5	5	48.5	56.5	PASS	

^{1.} Cyclic stage with 8-12 seconds per cycle.

9.2 Remarks

A single beyor of 2 ml flat polyethylene film was applied across the entire surface of the prepared roof deck in order to seal against air leakage. This plastic film contacted all surfaces of the panels and/or clips and id not interfere with air passage to the specimen or the movement of adjacent parts. No signs of the were noticed during class 30, 60, and 90 of the UL 580 test. No failures were observed in any components of the roof system or in any of the fasteners used to attach the roof system to the prepared structural roof frame.



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075
Architectural Testing ARCHTEST.COM

Test Report #: B5170.08-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 4 Page: 5 of 6

10.0 UL 1897 TEST RESULTS

10.1 Failure Test Load Data

Table 11 provides the failure test load data.

Table 11: Detailed Test Results of the Optional Failure Test

rable 11. Detailed rest results of the Optional Fallare rest					
Test	Pressure	Negative	Positive	Combined	Status
Phase	Duration (min)	Pressure (psf)	Pressure (psf)	Pressure (psf)	Status
1	1	30	48.5	78.5	RASS
2	1	45	48.5	93.5	RASS
3	1	60	48.5	108.5	PASS
4	1	75	48.5	123.5	PASS
5	1	90	48.5	138	PASS
6	1	105	48.5	153.5	PASS
7	1	120	48.5	68.5	PASS
8	1	135	48.5	183.5	PASS
9	1	150	48.5	198.5	PASS
10	1	165	48.5 (18)	213.5	PASS
11	1	180	48.5	228.5	PASS
12	1	195	A85.5	243.5	FAIL

10.2 Remarks

The highest combined pressure the test specimen successfully resisted for 1 minute was 228.5 psf. The specimen failed due to seam buckling at the middle section of an outer panel. The failure occurred while the specimen was being ramped up to a sustained combined pressure of 243.5 psf.

11.0 CERTIFICATION AND DISCLAIMER STATEMENT

All tests performed on this test specifien were conducted in accordance with the specifications of the applicable codes, standards and test methods listed below by ATI. ATI does not have, nor does it intend to acquire or will it acquire, a financial interest in any company manufacturing or distributing products tested at ATI. ATI is not comed, operated or controlled by any company manufacturing or distributing products it tests. This report is only intended for the use of the entity named in Section 1.0 of this report. Detailed assembly drawings showing panel/clip thicknesses, panel/clip profiles, accessories, fasteners and all other application are on file and have been compared to the test specimen submitted. ATI will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by ATI for the entire test record retention period.

If the specimen contains glazing, no conclusions of any kind regarding the adequacy or inadequacy of glass in any glazed test specimen can be made. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen tested. This report may not be reproduced, except in full, without the written approval of ATI.



Test Report #: B5170.08-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 4 Page: 6 of 6

12.0 APPLICABLE CODES, STANDARDS, AND TEST METHODS

UL 580 - Tests for Uplift Resistance of Roof Assemblies UL 1897 - Uplift Tests for Roof Covering Systems

13.0

ATT LEW ATT LE

ENGINEER OF RECORD

ally Signed by: Vinu Abraham
Vinu J. Abraham, P.E.

3/2/2012

REPORT WRITER

Angela Abramczyk

3/2/2012