

ASTM E1680 & ASTM E 1646 TEST REPORT

Rendered to:

SHEFFIELD METALS INTERNATIONAL

MODEL DESIGNATION: SMI 2" Mechanical Seam over B-Deck w/ISO PRODUCT TYPE: Standing Seam Roof System (24 Ga. Steel)

This report contains in its entirety:

Cover Page: 1 page **Report Body:** 6 pages

No. 53820

Intimum A A Dam

STATE OF

SONALEW MONALEW

Digitally Signed by: Vinu Abraham

2012.03.08 12:33:24

-05'00'

Report No.: B5170.19-450-18

Test Dates: 2/3-6/12 **Report Date:** 3/2/12

Test Report Retention End Date: 3/2/16



Test Report #: B5170.19-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 9A Page: 1 of 6

Sheffield Metals International

SMI 2" Mechanical Seam over B-Deck w/ISO (ASTM E1680 & ASTM E 1646)

Test Report #: B5170.19-450-18

1.0	MANUFACTURER'S ID	OB.	
1.1	<u>Name of Applicant</u> :	Sheffield Metals International 5467 Evergreen Parkway Sheffield Village, OH 44054 Voice: 904.413.7425	MECHICAL
1.2	<u>Contact Person:</u>	Jim Mitchell	W.LHES.

2.0 LABORATORY IDENTIFICATION

2.1 Test Notification #: N/A

2.2 <u>Lab Certifications</u>: Miami-Dade County (05-1014 Building Code

(TST1527); IAS (TL-244); AAMA; WDMA; Keystone Certifications; Texas Decertment of Insurance

3.0 SCOPE OF WORK

3.1 <u>Introduction</u>: Sheffield Metals International retained Architectural Testing, Inc.

(ATI) to conduct air infiltration and water penetration testing on their SMI & Mechanical Seam over B-Deck w/ISO System per

the requirements of ASTM.

3.2 <u>Report Information</u>: Table provides the test dates for this specimen.

Table 1: Specimen Test Dates

rable it opecanien rest bates				
Mock-Up		Specimen #	Test Dates	
	SMI 2" Mechanical Seam	٥٨	2/3/2012 -	
	over B-Deck w/ISO	9A	2/6/2012	

4.0 PRODUCT IDENTIFICATION

4.1 <u>Product Type</u>: Standing Seam Roof System

4.2 <u>Model Designation</u> SMI 2" Mechanical Seam over B-Deck w/ISO

4.3 Overall Size: 69" (wide) x 113" (long) – roof frame

4.4 General Description: This specimen consisted of a 69" x 113" roof frame sheathed

with a single layer of 22 ga. B-deck installed into A36 steel. This was followed by a single layer each of insulation, felt paper and moisture/fire barrier. The roofing panels were fastened over the

moisture/fire barrier.

4.5 Sheffield Metals provided the test specimen.



Test Report #: B5170.19-450-18

Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016 Specimen #: 9A

Page: 2 of 6

5.0 **COMPONENT DESCRIPTION**

5.1 **B-Deck Details:**

Table 2 provides the details of the B-Deck.

Table 2: B-Deck Details

	Table 21 b beek betails
Item	Description
22 ga. B-Deck	Each B-Deck panel was fabricated from 22 ga. (thickness = $0.030''$) ASTM A6535S GRD33 steel and had a G60 galvanized coating applied to it. Each finished B-Deck panel was 36" (wide) x 120" (long) and featured 6 ribs that were each 3-1/2" (w) and $\frac{1}{12}$ (h).

5.2

(wide) x 120" (long) and featured 6 rips that were each 3-1/2" (w) and cay 2" (n).				
Accessories: Table 3 provides a description of the accessories used in the test specimen.				
Table 3: Accessories				
Item	Description			
Insulation	H-Shield 1" thick polyiso insulation NOTE: The insulation was obtained in $4' \times 4'$ sheets and trimmed as necessary when assembling the test specimens.			
Felt paper	30# Asphalt saturated organic paper (ASTM D226) meeting type II requirements			
Moisture/fire barrier	wersaShield®			

Metal Roof System: 5.3

Table 4 provides the metal roof system components used in the test specimen.

Table 4: Metal Roof System Components

Table 4. Metal Components				
Item	Overall Cross-Section	Material	Coil Width	Description
Mechanical Seam Panel	Please see part drawing labeled "SMP2" Mechanical Seam" for dimensions	24 ga. steel	24"	Each panel had an effective covering width of 18". Each finished roof panel was 111" (long) and featured two (2), 2" vertical legs (one w/return flap).
Clip Assembly (Butterfly Base 2" – Part # 1126600)	2.008 x 1.750" x 4.500" (long)	18 ga. G-90 galvanized steel	N/A	Each expansion-type butterfly panel clip consisted of a "base" and a "tab" that were each fabricated from two
Clip Assembly (Butterfly Tab 2007) Part # 1103097)	5.000" (long) x 0.900" (tall) with two return flaps that were 0.400" (wide)	22 ga. G-90 galvanized steel	N/A	different thickness of steel. Each clip "base" had two holes capable of accommodating #12 pancake head screws.



Test Report #: B5170.19-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016

Specimen #: 9A Page: 3 of 6

6.0 SPECIMEN CONSTRUCTION

6.1 <u>Specimen Construction:</u>

Table 5 provides the specimen construction.

Table 5: Specimen Construction

	Table 5: Specimen Construction
Location	Description
B-deck to roof frame	The B-deck panels were mechanically attached to the steel frame members using #12 x 1-1/4" self-drilling SMS spaced at 6" on center. The B-deck panels were attached at the perimeter. Adjacent panels were mechanically attached to one another at the overlap locations using #12 x 1-1/4" self-drilling SMS spaced at 6" on center.
Insulation	A single layer of H-Shield 1" thick polyiso insulation was mechanically attached to the B-deck using #12 x 1-5/8" self-drilling PH Dekfast™ Fasteners through 2-7/8" x 2-7/8" insulation plates. There were five (5) fasteners used to secure each piece of insulation. These fasteners were located 8" from each corner and at the center. Additionally, the insulation was mechanically secured to the steel deck via the fasteners that attach the panel clips (described below).
Felt paper	A single layer of felt paper with 4" laps was tacked in place across the top of the B-deck and was secured when the metal roofing was installed.
Moisture/fire	A single layer of VersaShield® with 4" laps was tacked in place across the top of the felt
barrier	paper and was secured when the metal coofing was installed.
Roof panel	Each finished roof panel featured an inside leg and an outside leg. These legs were overlapped around a butterfly clip base/tab assembly. These clip assemblies were spaced 7" from each panel end and at 2" on center thereafter. Each clip was mechanically attached to the B-deck substrate using two (2), #12 x 1-5/8" self-drilling PH Dekfast™ Fasteners. The legs were then mechanically seamed 180 degrees.
Partial	The partial panel cut ecoses at the perimeter of the roof panel assembly were attached to
panel cut	the B-deck substrate wing groups of two (2), #12 x 1-5/8" self-drilling PH Dekfast™
edges	Fasteners spaced 6" on center (two [2] fasteners in group were spaced 2" apart).
Panel ends	The panel ends at the perimeter of the roof panel assembly were attached to the B-deck substrate using a single row of #12 x 1-5/8" self-drilling PH Dekfast™ Fasteners spaced at 6" on center.

7.0 TEST RESULT SUMMARY

Table 6 provides a summary of the test results for all tests conducted per ASTM E 1680 and ASTM E 1646. The temperature during testing was 76°F.

Table 6: Summary of Test Results

rable of barrinary of reservesales			
Specimen # Test Method		Test Conditions	Conclusion
0.4	Air Leakage Test (ASTM E 1680)	+1.57/-1.57 psf	N/A
9A	Water Penetration Test (ASTM E 1646)	12.00 psf	PASS

6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075 Architectural Testing ARCHTEST.COM Test Report #: B5170.19-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 9A Page: 4 of 6

8.0 **TEST SEQUENCE**

Table 7 provides the test sequence for the specimen.

Table 7: Test Sequence

Specimen # 9A

- 1. Air Leakage Test Preloads
 - a Positive Preload
 - b. Negative Preload
 - c. Positive Preload
 - d. Negative Preload
 - e. Positive Preload
 - f. Negative Preload
- 2. Air Leakage Test Air Infiltration
- 3. Air Leakage Test Air Exfiltration

Water Penetration Test

9.0 **TEST RESULTS**

9.1 Air Leakage Test

> **Preload Pressures** 9.1.1

Table 8 provides the pressure differences exerted across the test specimen during the preloads.

Table 8: Preload Pressures


WK	Test Pressure
<u>""</u>	(psf)
Positive	45.88
Regative	45.88
ositive	45.88
Negative Negative	45.88
Positive	45.88
Negative	45.88

9.1.2 **Results**

Table 9 provides the results for the air leakage test.

Table 9: Air Leakage Test Results

rable 9. All Leakage rest Results		
Test Pressure		Measured
	(psf)	(cfm/ft ²)
Air infiltration	+1.57	0.03
Air exfiltration	-1.57	0.02



Test Report #: B5170.19-450-18 Report Date: 3/2/2012

Test Report Retention End Date: 3/2/2016 Specimen #: 9A

Page: 5 of 6

9.2 <u>Water Penetration Test</u>

9.2.1 Results

Table 10 provides the results for the water penetration test.

Table 10: Water Penetration Test Results

Table 101 Water Ferredation Fest Results						
Test Pressure	Spray Rate	Test Duration	Ponded Water Depth	Conclusion	1	
(psf)	(gph/ft²)	(minutes)	(in.)	Conclusion		
12.00	5.0	15.00	0.75	Pass		

9.2.2 Conclusion

ATI observed zero (0) water infiltration through the test specimen; as such, this test specimen satisfies the requirements of ASTM E 1646.

10.0 CERTIFICATION AND DISCLAIMER STATEMENT

All tests performed on this test specimen were conducted in accordance with the specifications of the applicable codes, standards and test methods listed below by ATK ATI does not have, nor does it intend to acquire or will it acquire, a financial interest in any company manufacturing or distributing products tested at ATI. ATI is not owned, operated or controlled by any company manufacturing or distributing products it tests. This report is only intended for the use of the entity named in Section 1.0 of this report. Detailed assembly drawings showing panel/clip thicknesses, panel/clip profiles, accessories, fasteners and all other applicable layouts are on file and have been compared to the test specimen submitted. ATI will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by ATI for the entire test record retention period.

If test specimen contains glazing, no conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test speciment can be made. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen tested. This report may not be reproduced, except in full, without the written approval of ATI.

11.0 APPLICABLE CODES, STANDARDS, AND TEST METHODS

ASTM E 1680 – Standard Test Method for Rate of Air Leakage Through Exterior Metal Roof Panel Systems ASTM E 1646 – Standard Test Method for Water Penetration of Exterior Metal Roof Panel Systems by Uniform State Air Pressure Difference

12.0 WITNESSES (ALL OR PARTIAL)

Vice President - Southeast Region	ATI
Director – Regional Operations	ATI
Operations Engineer	ATI
Technician	ATI
Technician	ATI
	Director — Regional Operations Operations Engineer Technician



6655 Garden Road Riviera Beach, FL 33404 P: 888.477.2454

F: 561.881.0075
Architectural Testing ARCHTEST.COM

Test Report #: B5170.19-450-18

Report Date: 3/2/2012 Test Report Retention End Date: 3/2/2016

> Specimen #: 9A Page: 6 of 6

THE REPORT OF CHARGE METERS OF THE PROPERTY OF

ENGINEER OF RECORD

Digitally Signed by: Vinu Abraham
Vinu J. Abraham, P.E.

3/2/2012

Digitally Signed by: Angela Abramczyk

Angela Abramczyk

3/2/2012

REPORT WRITER