

## UL 580 & UL 1897 TEST REPORT

Report No.: C9079.02-450-44

#### Rendered to:

SHEFFIELD METALS INTERNATIONAL Sheffield Village, Ohio

PRODUCT TYPE: Standing Seam Roof System (245a. Steel)
SERIES/MODEL: SMI 2.0 SCH Mechanical Seam Over 22 GA. B-Deck

2014.02.18 11:04:03 -05'00'

 Test Date:
 12/12/13

 Report Date:
 02/11/14

 Test Record Retention Date:
 12/12/17

**Architectural Testing** 

Test Report No.: C9079.02-450-44

Report Date: 02/11/14

Test Record Retention End Date: 12/12/17

Page 1 of 5

**1.0 Report Issued To:** Sheffield Metals International

> 5467 Evergreen Parkway Sheffield Village, Ohio 44054

Voice: 904.413.7425 Contact: Jim Mitchell

2.0 Test Laboratory: Architectural Testing, Inc.

2658 Electronics Way

West Palm Beach, Florida 33407

561.881.0020

#### **3.0 Project Summary:**

**3.1 Product Type**: Standing Seam Roof System

ONSENT FROM THE SMITECHNICAL DEPT. 3.2 Series/Model: SMI 2.0 SCH Mechanical Seam Over 22 Ga. B- Deck

**3.3 Compliance Statement**: Results obtained are tested values and were secured by using the designated test methods. The test specimen was tested in accordance with UL 580 and UL 1897 and achieved an ultimate test load of -127 psf.

**3.4 Test Date**: 12/12/2013

3.5 Test Location: Architectural Testing, Inc. test facility in West Palm Beach, Florida.

test specimen was provided by the client. 3.6 Test Sample Source: Representative samples of the test specimens will be retained by Architectural Testing for a minimum four years from the test completion date.

**3.7 Test Specimen Installation**: The test specimen was installed by representatives from Sheffield Metals International.

**3.8 Drawing Reference**: The test specimen drawings have been reviewed by Architectual Testing and are representative of the test specimen reported herein. Test specimen construction was verified by Architectural Testing per the drawings located in Appendix E. Any deviations are documented herein or on the drawings.

Company

## 9.4.ist of Official Observers:

Name

Vinu Abraham , P.E.	Architectural Testing, Inc.
Jeff McGovern	Architectural Testing, Inc.
John Spallina	Architectural Testing, Inc.
Alan Rule	Architectural Testing, Inc.



Report Date: 02/11/14

Test Record Retention End Date: 12/12/17

Page 2 of 5

## **4.0 Test Specification(s)**:

UL 580, Underwriters Laboratories, Inc., Standard for Safety, Tests for Uplift Resistance of Roof Assemblies, (Fifth Edition November 2, 2006, revised through July 9, 2009)

UL 1897, Underwriters Laboratories, Inc., UL Standard for Safety for Uplift for Roof Covering Systems (Fifth Edition March 11, 2004, revised through May 22, 2008)

The purpose of this test is to evaluate the comparative resistance of roof assemblies to positive and negative pressures. This test simulates the effects of wind gusts by use of oscillating exterior pressure and constant interior pressures.

## **5.0 Test Specimen Description:**

#### **5.1 Product Sizes**:

Test Specimen #1:

Overall Area:	Width		Length	
100.0 ft <sup>2</sup> (9.3m <sup>2</sup> )	inches	millimeters	inches	millimeters
Overall size	120	3048	120	3048
Panel Size	18 3/4	476	120	3048

**5.2 Test Deck Construction.** The 10' 0" wide by 10' 0" long by 1' 3" deep test frame was fabricated from 15 by 33.9 steel channels. Two W6 x 12 steel purlins were located 30" from each side of the test frame (purlin spacing of 5' on center). A 1/4" steel plate was welded to each end of the purlins and bolted to the frame using two 1/2" x 1-1/2 bolts. Continuous 3-1/2" by 3-1/2" by 3/16" thick L-shaped steel angle was holted around the interior perimeter of the test frame.



Report Date: 02/11/14

Test Record Retention End Date: 12/12/17

Page 3 of 5

# **5.0 Test Specimen Description**: (Continued)

## **5.3 Roof System:**

Test Specimen #1:				
Components	Details	Attachment Method (		
Type "B" roof decking	22 gauge steel roof decking, measuring 1-1/2" high and 10' long. Three full width panels (36" wide) and one partial width panel (12" wide) were lapped and utilized.	Seams were secured through the valleys of the deck with #12 x 3/4 long hex head self-drilling screws, spaced 6" on center. The deck was secured to the perimeter angle and the steel purlin through the valleys of the deck with #12 x 1-1/4" long hex head self-drilling screws, spaced 6" on center.		
30# Asphalt saturated		TWRITE		
organic paper (ASTM D 226) meeting type II	A single layer of felt paper, lapped 4 inches, attached to the B-Deck substrate.	The test paper was secured using #12 x 1 screws with tin tabs spaced 22" at the seams and center of each sheet.		
requirements.	MAIN.			
SMI 2.0 SCH Mechanical Seam roof panel	The panels were constructed from 24 Ga steel. Six full width penels measuring 18 3/4" wide by 120" long and two partial panels measuring 3" wide by 120" long were tested.	The roof panels were secured to the B-deck utilizing 2" Float Clips. The panels overlapped each other and were seamed using a hand seamer to 90° (stage one) and then using a mechanical seamer to 180° (stage two). The perimeter of the roof deck was secured with #12 x 1" pancake screws. The screws were spaced 2" on center at the panel ends and pairs of screws 2" apart were spaced 4" on center at the panel sides.		
LISE Clips	The G-90 galvanized 2" Float Clips measured 2.4" high by 4.3" wide and consisted of a 16 Ga. base and a 22 Ga. tab.	Each clip was attached using two #12 x 1" pancake screws. A clip was used at each panel end and 24" on center thereafter		



Report Date: 02/11/14

Test Record Retention End Date: 12/12/17

Page 4 of 5

**6.0 Test Results**: One assembly was tested per UL 580 and UL 1897. The following summarizes observations made during the test at each class rating.

Test Specimen #1:

Test Class	Test Phase	Results	
Class 30	No visible damage to the system	DageED	
Phases 1-5	Reference Table #1 for deflection measurements	PASSED	
Class 60	No visible damage to the system	PASSED	
Phases 1-5	Reference Table #2 for deflection measurements	Y PASSED	
Class 90	No visible damage to the system	PASSED	
Phases 1-5	Reference Table #3 for deflection measurements	PASSED	
Supplemental	No visible damage to the system	D 4 66FF	
Loads -112 psf to -127 psf	Reference Table #4 for deflection measurements	PASSED	
Supplemental	Clip fasteners pulled out the B-deck while		
Loads	increasing pressure to 142 psf.	FAILED	
-142 psf	i Alar		

#### Notes:

- Reference Chart #1 located in Appendix A for test pressures and load durations.
- Reference Sketch #1 in Appendix B for location of deflection measurement devices.
- Deflection measurements are included in Table #1 through #4 in Appendix C of this test report.

General Test Note: A loose fitting, pleated 2-mil plastic film was utilized to assist in obtaining uniform pressure on the roof system. The plastic film was located between the panels and the uniform pressure to facilitate testing of the panels. In our opinion, this did not influence test results.



Report Date: 02/11/14

Test Record Retention End Date: 12/12/17

Page 5 of 5

Architectural Testing will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by Architectural Testing, Inc. for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endowsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen tested. This report may not be reproduced, except in full without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, Inc.

Digitally Signed by: John Spallina

John Spallina

Vince Abraham, P.E.

Wise President – Southeast Region

This report produced from controlled document template ATI 00512, issued 04/26/11.